

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 2 Twp. 21 Rge. 13 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW SE $\frac{1}{4}$

Lease Owner Armer Drilling Company, Inc.

Lease Name Address "B" Well No. 1

Office Address 710 Petroleum Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed Aug. 13 19. 49

Application for plugging filed Dec. 9 19. 49

Application for plugging approved Dec. 9 19. 49

Plugging commenced Dec. 9 19. 49

Plugging completed Dec. 17 19. 49

Reason for abandonment of well or producing formation well depleted

If a producing well is abandoned, date of last production Dec. 2 19. 49

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Arbuckle Depth to top 3522 Bottom 3549 Total Depth of Well 3549 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	dry	3522	3549	8-5/8 5 1/2	200 3523	1867'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with chat from bottom to 3515 ft. dumped 5 sacks cement in 5 1/2" at 3515 ft. Ripped off and pulled 5 1/2", filled with mud to 200 ft. Rock bridge and 15 sacks cement at 200 ft. filled with mud to 30 ft. Set bridge and 10 sacks cement at surface.

JAN 27 1950
1-27-50
STATE CORPORATION COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Armer Drilling Company, Inc.
Address 710 Petroleum Bldg.

STATE OF Kansas, COUNTY OF Sedgwick
L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. ARMER DRILLING COMPANY, INC.

(Signature) By L. C. Sponenberg

710 Petroleum Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of January, 19. 50

Hazel W. Eaton
Notary Public.

My commission expires Sept. 17, 1951

PLUGGING
FILE SEC 2 T 21 R 30
BOOK PAGE 130 LINE 38

Owner's: Armer Drilling Company, Inc.
National Cooperative Refinery Assn.
Contractor: Armer Drilling Company, Inc.
Drilling Commenced: 7/25/49
Drilling Completed: 8/6/49
Elevation: 1870 D.F. - 1067 Gr.
Lotary #1

Farm: Address #1 B
Location: NW, NW, SE, Sec. 2-21-15W
Stafford County, Kansas
Casing Record: 8-5/8" @ 200' cemented with
150 Sack Cement

(figures below indicate bottoms)

Sand	185
Shale & shells	200
Sand & Shale	230
Red Bed	693
Anhydrite	730
Shale & Shells	755
Shale & Lime	1015
Shale & Shells	1200
Salt	1315
Shale	1325
Shale & Shells	1725
Lime	1830
Lime & Shale	2930
Lime	3179
Lime	3520
Lime	3526 Total Depth

3528 = 3526 T.D. corrected drill pipe measurement
5 1/2" casing cemented @ 3523 (corrected) with
75 sacks cement.

FORMATION TOPS:

Hestner	3111
Lansing-Kansas City	3250
Conglomerate	3505
Simpson	3509
Arbuckle	3522 Corrected

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER DRILLING COMPANY, INC.

JAN 27 1950

L. C. Spinning

STATE OF KANSAS

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State, this 9th day of August, 1949.

Dorothy Marshall
Notary Public

My Commission Expires :

My Commission Expires April 19, 1952

PLU...
FILE SEC 2 T 21 R 130
BOOK PAGE 130 LINE 3-8