


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail Report to:  
Conservation Division  
State Corporation Commission  
211 Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 2 Twp. 21S Rge. (E) 13 (W)  
Location as "NE/CNW/SW" or footage from lines SW NW SW  
Lease Owner CHIEF DRILLING CO., INC.  
Lease Name ADDRESS Well No. 1  
Office Address P.O. Box 797, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Sept. 18 19 61  
Application for plugging filed Sept. 18 19 61  
Application for plugging approved Sept. 21 19 61  
Plugging commenced Sept. 21 19 61  
Plugging completed Sept. 27 19 61  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel, Pretty Prairie, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3537 Feet  
Show depth and thickness of all water, oil and gas formations. Cable Tool T.D. 3572'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	227'	None
				5-1/2"	3533'	1430'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back to 3510' with sand, dumped 5 sacks cement  
Set plug at 225' - 10' rock bridge dumped 1 sack of Colseal.  
Dumped 20 sacks cement. Mudded hole up to 35'. Put in 10  
sacks cement

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 10 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Central Pipe Pulling Co.  
Address 1416 Coolidge, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
W. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. Richard Hoover  
W. Richard Hoover, President  
P.O. Box 797, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 19 61

My commission expires June 18, 1963

Dorothy B. John  
Dorothy B. John Notary Public.



WELL LOG

Chief Drilling Co., Inc.  
P.O. Box 797  
Great Bend, Kansas

No. 1 Andrews  
SW NW SE Sec. 2-21-134  
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 8-21-61  
Completed: 9-3-61

CASING RECORD: 3-5/8" @ 227' with 235 sacks Sunset Cement.  
5-1/2" @ 3533' with 75 sacks common cement.

FORMATION	FROM	TO	ELEVATION
Sand	0	135	1872' Cr.
Shale	180	227	1874' D.F.
Red bed	227	340	1877' E.S.
Shale & Sand	340	695	
Anhydrite	695	723	
Shale	723	1060	
Shale and Shells	1060	1535	
Shale & Lime Strata	1535	1560	
Lime	1560	1745	
Lime and Shale	1745	2764	
Lime	2764	3125	
Lime and Shale	3125	3174	
Shale	3174	3271	
Lime	3271	3501	
Conglomerate	3501	3531	
Dolomite	3531	3537	
Total Depth	3537		

FORMATION TOPS

Anhydrite	695
Topota	2764
Hoebner	3125
Toronto	3156
Douglas	3174
Brown Lime	3261
Lansing	3271
Face Kansas City	3407
Conglomerate	3501
Artuckle	3531

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SW NW SE Sec. 2-21-134, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.  
Original Signed By

*V. Michael Hoover*  
V. Michael Hoover - President

Subscribed and sworn to before me this 12th day of September, 1961

*Dorothy B. Johns*  
Dorothy B. Johns, Notary Public

My commission expires: June 18, 1963