


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County, Sec. 2 Twp. 21 Rge. 13 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Circle Oil Co.
Lease Name Address Well No. 1
Office Address 500 Bitting Bldg. Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed _____ May 14, 1968
Application for plugging approved _____ May 17, 1968
Plugging commenced _____ May 16, 1968
Plugging completed _____ May 19, 1968
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	208'	None
				5 1/2	3529'	2424'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3530' to 3250'. Mixed and dumped 5 sx. of cement from 3250' to 3210'. Pulled casing. Mudded hole to 200'. Set 10' rock bridge from 200' to 190'. Mixed and dumped 25 sx. of cement from 190' to 115'. Mudded hole from 115' to 40'. Set 10' rock bridge from 40' to 30'. Mixed and dumped 10 sx. of cement from 30' to base of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1968
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling Inc.
Address Box 1082 Great Bend, Ks. 62530

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 28th day of May 1968



Louise K. Whitted
Louise K. Whitted - Notary Public.

DRILLERS LOG

No. 1 Address

CASING RECORD:	COMPANY:	Circle Oil Company	DESCRIPTION:
8 5/8" @ 208'	CONTRACTOR:	Red Tiger Drilling Co.	SE SW SW
w/225 sx cement	COMMENCED:	September 29, 1964	2-21S-13W
5 1/2" @ 3529'	COMPLETED:	October 7, 1964	Stafford Co., Kansas
w/90 sx cement			ELEVATION: 1870 DF
TOTAL DEPTH: 3530'			1873 RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface	0	40	
Sand	40	100	
Shale & Sand	100	140	
Clay & Shale	140	210	
Redbed & Shale	210	702	
Anhydrite	702	727	
Shale & Shells	727	1520	
Shale Shells & Lime	1520	1810	
Lime & Shale	1810	2940	
Lime	2940	3490	
Cherty Limo	3490	3520	
Limo	3520	3530	

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1968
CONSERVATION DIVISION
Wichita, Kansas

Top perforation 3277-81.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Head
Maxine V. Head

Subscribed and sworn to before me this 8th day of October, 1964.

Jean Hollas
Notary Public

My Commission Expires:

5-22-66