

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 July 2014 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 5107 Name: H-30, Inc. Address 1: 13735 Pinnacle Drive Address 2: City: Wichita State: KS Zip: 67230 + 1545 Contact Person: Mr. Dean Britting Phone: (316) 644-7299 Type of Well: (Check one) [X] Oil Well [] Gas Well [] OG [] D&A [] Cathodic [] Water Supply Well [] Other: [] SWD Permit #: [] ENHR Permit #: [] Gas Storage Permit #: Is ACO-1 filed? [] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): List All (If needed attach another sheet) Lansing Depth to Top: 3932 Bottom: 3968 T.D. 4400

API No. 15 - 15-063-20864-00-00 Spot Description: C NW SW SW Sec. 19 Twp. 14 S. R. 27 [] East [X] West 990 Feet from [] North [X] South Line of Section 4,950 Feet from [X] East [] West Line of Section Footages Calculated from Nearest Outside Section Corner: [] NE [] NW [X] SE [] SW County: Gove Lease Name: Jacobs A Well #: 1 Date Well Completed: 01/01/1985 The plugging proposal was approved on: 06/01/2017 (Date) by: Case Morris (KCC District Agent's Name) Plugging Commenced: 06/20/2017 Plugging Completed: 06/20/2017

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Lansing, Oil/Water, Surface, 8.625, 218, 0. Row 2: Production, 5.50, 4375, 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Arrived on location @ 7:30. Tubing, pulling unit, and water arrived on location @ 7:45. Spotted rig in and RU. TIH w/ 124 jts of 2 3/8" tubing to 3906.49'. 1st plug @ (3906.49') Mixed and pumped 13 sxs of gel & 65 sxs of pozmix (60/40-4% gel) and 300# of hulls. Pulled 61 jts to 2341.39'. 2nd plug @ 2341.39'. Mixed and pumped 250 sxs of 60/40 pozmix (60/40-4%) to surface. Pumped 5 bbls of water to clean the tubing and pulled the remainder of the tubing. Topped off the casing with an additional 20 sxs, tied onto the Braden Head and pumped 5 sxs down the surface (Pressured to 300#). Job was done @ 1:30 pm (06/20/2017).

Cementers: Quality Cementing (Russell-Ticket #1570) Company Representative: Jeffrey A. Burk, Consulting Geologist State Representative: Mr. Marvin Mills (KCC-Hays Office)

KCC WICHITA AUG 11 2017 [checkmark]

RECEIVED

Plugging Contractor License #: 6426 Name: Express Well Service & Supply, Inc. Address 1: P.O. Box #19 Address 2: City: Victoria State: KS Zip: 67671 + 0019 Phone: (785) 735-9405

Name of Party Responsible for Plugging Fees: H-30, Inc. (Dean E. Britting-Northstar Investments)

State of Kansas County, Sedgwick, ss.

Jeffrey A. Burk, Consulting Geologist [checkmark] Employee of Operator or [] Operator on above-described well, (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]