

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 9 TWP. 21S RGE. 23 NE/W
Location as in quarters or footage from lines:
C NE NW

Lease Owner The Brown Company
Lease Name Frusher Well No. 1
Office Address 7333 E. 22nd St. - #6, Wichita, Ks. 67226
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 7-26-83
Application for plugging filed 7-26-83
Plugging commenced 7-26-83
Plugging completed 7-26-83
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well N/A

Producing formation _____ Depth to top _____ bottom _____ T.D. 4565'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	490'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Spot 50 sx cement @ 1530' thru drillpipe
Spot 40 sx cement @ 540' thru drillpipe
Solid bridge plug @ 40', 1/2 sx hulls, spot 10 sx cement
thru drillpipe.
15 sx cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1983

CONSERVATION DIVISION
Wichita, Kansas

8-19-83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.


(Signature) Ernest Sifford
401 E. Douglas #500 Wichita
(Address) Kansas 67202

SUBSCRIBED AND SWORN TO before me this 15th day of August, 19 83

My Commission expires:

CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Expires Sept. 5, 1984

Carolyn J. Tjaden
Carolyn J. Tjaden Notary Public.



WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: THE BROWN CO., 7333 East 22nd Street - #6, Wichita, Kansas 67226

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name FRUSHER Well No. 1

Sec. 9 T. 21 South R. 23 West Spot C NE NW

County Hodgeman State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 490' with 300 sx. 2% Gel 3% CC

Production: @ with sx.

Type Well: D & A Total Depth 4565'

Drilling Commenced 7-16-83 Drilling Completed 7-26-83

Formation	From	To	Tops
Cellar	0	7	
Shale	7	760	
Sand, Shale	760	1484	
Shale, Lime	1484	3200	
Lime, Shale	3200	3390	
Shale, Lime	3390	3733	
Lime, Shale	3733	3907	
Lime	3907	4565	

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1983

CONSERVATION DIVISION
Wichita, Kansas