

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-21263-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 35-25S-8E  
1465 feet from N Section Line, 330 feet from W Section Line  
Lease Name: LADD C Well #: 9  
County: GREENWOOD Total Vertical Depth: 2583 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comment
<u>5697</u>	PROD	4.5	2502		50 SX
Op Name: <u>JACKSON BROTHERS, L.L.C.</u>	SURF	7	68		50 SX
Address: <u>116 E 3RD ST</u> <u>EUREKA, KS 67045</u>					

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/18/2017 8:00 AM  
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC  
Proposal Rcvd. from: ROSCOE G. JACKSON II Company: \_\_\_\_\_ Phone: (620) 583-5122

Proposed Plugging Method: 1. 50 ft. cement plug inside 4.500" casing at 2420-2370 ft. 2. 50 ft. cement plug inside and outside 4.500" at 1200-1150 ft. 3. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: NONE  
Date/Time Plugging Completed: 08/20/2017 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran dump baler to 2420', spotted 7 sxs cement, ran tubing to 1200', pumped 20 sxs cement, pulled tubing to 250', pumped 55 sxs cement to surface. gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2455	2467		

RECEIVED  
KCC DIST # 3  
AUG 28 2017  
CHANUTE, KS

mtt

INVOICED  
AUG 31 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern  
(TECHNICIAN)

Received 22 August 2017

810 E 7<sup>th</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



Cement or Acid Field Report  
 Ticket No. **3442**  
 Foreman Steve Mead  
 Camp Eureka KS

15-073-21263-00-00

Date	Cust ID #	Lease & Well Number	Section	Township	Range	County	State	
5-20-17	1008	Loddc #9	35	25S	8E	Greenwood	KS	
Customer Jackson Brothers LLC			Unit #		Driver		Unit #	Driver
Mailing Address 116 E 2nd			102		Pick			
City Eureka			112		STEVEN			
State KS			144		DAVE			
Zip Code 67045								

Job Type PTA Sidwell Hole Depth \_\_\_\_\_ Slurry Vol \_\_\_\_\_ Tubing 2 3/8  
 Casing Depth \_\_\_\_\_ Hole Size 6 1/2 Slurry Wt \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt 4 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: SAFETY Meeting. Rig up to 2 3/8 Tubing. Break Circulation w/ Fresh Water. Spot 25K at 1200' well on Rig. Pull out Tubing. Rig up to 4 1/2 casing. Break Circulation w/ Fresh Water. Mix 55 SKS cement 250' to surface inside & back side of 4 1/2 casing. Cement Fall down 25' inside 4 1/2 casing. Wait 1 1/2 hrs. Top well off. Job Complete.

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	15	Mileage	3.93	59.25
C203	255 SKS	60/40 Poz mix cement	12.75	956.25
C206	250 gal	GR 4%	.20	50.00
C108A	3.23 ton	Ton mileage Bulk Truck	M/C	345.00
C113	3 hrs	8000 l uac truck	85.00	255.00
C224	2500 gal	CITY WATER	1000/1000	25.00
		Total 2623.54		
		5% Discount 131.18		
		2492.36		
			Sub Total	2440.50
			Sales Tax	183.04
			7.50%	

Authorization Steve H. Jackson II Title CO-MANAGER Total 2623.54

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.