

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-20511-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 8-14S-14W  
4315 feet from S Section Line, 457 feet from E Section Line  
Lease Name: ANSCHUTZ Well #: 3  
County: RUSSELL Total Vertical Depth: 2520 feet

Operator License No.: 30737  
Op Name: M.A. YOST OPERATIONS, INC  
Address: PO BOX 811  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2515		
SURF	8.625	197		140 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2017 7:45 AM  
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.  
Proposal Rcvd. from: JACK YOST Company: M.A. YOST OPERATIONS, INC DBA Phone: (785) 483-0271

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/20/2017 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 900', 460' and 200'. Ran tubing to 2400' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1200' and pumped 125 sx cement w/100 # hulls. Circulated cement to pit. POOH. Hooked to casing and pumped 25 sx cement at 350 psi. Hooked to braden head and pressured to 300 psi. No fluid was moved.

GPS: 38.85368 -098.89313

Perfs:

KCC WICHITA  
AUG 24 2017  
RECEIVED

Remarks: GLOBAL CEMENTING SERVICE TICKET # 3037

Plugged through: TBG

INVOICED  
AUG 31 2017

District: 04

Signed \_\_\_\_\_

*Ray Dinkel*

(TECHNICIAN)

CM

AUG 03 2017