

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-20950-00-00  
Spot: N2SWSW Sec/Twnshp/Rge: 11-16S-14W  
990 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: KARST Well #: 1  
County: BARTON Total Vertical Depth: 3383 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3362		
SURF	8.625	263		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/28/2017 10:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/28/2017 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 900' and 260'. Ran tubing to 3305' and pumped 14 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 60 sx cement w/200 # hulls. Pulled tubing to 900' and pumped 60 sx cement. Pulled tubing to 300'. Circulated cement to surface with 70 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe with 50 sx cement. Pressured up to 300 psi and shut in.

GPS: 38.66946 -098.84749

Perfs:

Top	Bot	Thru	Comments
3362	3383		

KCC WICHITA  
AUG 24 2017  
RECEIVED  
INVOICED  
AUG 31 2017

Remarks: HURRICANE SERVICES TICKET # 100779

Plugged through: TBG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

AUG 03 2017