

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-20635-00-00
Spot: NENESE **Sec/Twnshp/Rge:** 15-30S-8W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: LATTIMORE-RALL **Well #:** 1
County: KINGMAN **Total Vertical Depth:** 4218 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4259	2470	125 SX
SURF	8.625	209		165 SX

Well Type: GAS **UIC Docket No:** _____ **Date/Time to Plug:** 06/09/2017 8:00 AM
Plug Co. License No.: 34082 **Plug Co. Name:** ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY **Company:** PICKRELL DRILLING CO **Phone:** (620) 793-2316

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON **WitnessType:** PARTIAL
Date/Time Plugging Completed: 06/09/2017 4:00 PM **KCC Agent:** B. J. HOPE

Actual Plugging Report:

SET CIBP @ 4104 CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2470' PULLED CASING. RUN TUBING TO 1264' PUMPED 15 SX GEL, THEN SPOTTED 50 SX CEMENT. WAITED 2 HOURS TAGGED @ 1054' PULLED TUBING TO 800' SPOTTED 35 SX CEMENT. PULLED TUBING TO 250' CIRCULATED TO SURFACE WITH 100 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4164	4177		

Remarks: BASIC ENERGY PROVIDE CEMENT FOR THIS JOB.

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)

INVOICED
SEP 01 2017