

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-02037-00-00  
Spot: SESE Sec/Twnshp/Rge: 30-20S-13W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: MCGREEVEY Well #: 2  
County: BARTON Total Vertical Depth: 3367 feet

Operator License No.: 34278  
Op Name: SHAWN D. EVANS INC. DBA ACE OIL C  
Address: 18529 WALTERS RD PO BOX 606  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3366		100 SX
SURF	8.625	140		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2017 12:00 PM  
Plug Co. License No.: 34946 Plug Co. Name: ACE WELL SERVICE, INC.  
Proposal Rcvd. from: SHAWN EVANS Company: SHAWN D. EVANS INC. DBA ACE Phone: (785) 324-0502

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 1400 # gel. Well was squeezed. High cement around braden head with no access.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/14/2017 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 760'. Ran tubing to 3250' and pumped 14 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 60 sx cement w/200 # hulls. Pulled tubing to 800' and pumped 60 sx cement. Pulled tubing to 200'. Circulated cement to surface with 35 sx cement. Pulled tubing. Topped off with 5 sx cement.  
07/21/2017- Topped off with 10 sx cement dry.

GPS: 38.27707 -098.79497

Perfs:

KCC WICHITA  
AUG 24 2017  
RECEIVED

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

INVOICED  
SEP 01 2017

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

AUG 03 2017