

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21882-00-01
Spot: N2SWSWSW Sec/Twnshp/Rge: 20-27S-12W
480 feet from S Section Line, 4950 feet from E Section Line
Lease Name: CASPARI "A" Well #: #1 OWWO
County: PRATT Total Vertical Depth: 4466 feet

Operator License No.: 3959
Op Name: SIROKY OIL MANAGEMENT
Address: PO BOX 464
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3850		WITH 2 SX CMT
CIBP		4150		
COND	13.375	227		WITH 215 SX CMT
PROD	5.5	4355	1544	WITH 150 SX CMT
SURF	8.625	970		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2017 8:30 AM
Plug Co. License No.: 34484 Plug Co. Name: FOSSIL DRILLING, INC.
Proposal Revd. from: BRIAN SIROKY Company: FOSSIL DRILLING Phone: (620) 672-5625

Proposed Plugging Method: SET CIBP @ 3850' WITH 2 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 670' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/15/2017 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3850' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 970' WITH 50 SX CMT. 2ND PLUG AT 424' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT. LAID DOWN 1 JOINT & TOPPED OFF SURFACE PIPE WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4202	4227		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

INVOICED
SEP 01 2017

District: 01

Signed Stephan Pfeifer
SA (TECHNICIAN)

RECEIVED
AUG 18 2017
KCC DODGE CITY