

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23263-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 30-7S-22W
2240 feet from N Section Line, 360 feet from E Section Line
Lease Name: WEBB Well #: 1-30
County: GRAHAM Total Vertical Depth: 3900 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 200 W DOUGLAS AVE #725
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3896		165 SX
SURF	8.625	209		165 SX
T1	2.375	3765		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2017 9:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: ERIK HAGANS Company: VINCENT OIL CORPORATION DBA Phone: (620) 388-5858

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perforations: 3561' - 3564', 3566' - 3569', 3653' - 3657' and 3850' - 3851'.
Port Collar at 1903' w/310 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2017 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3570' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 2570' and pumped 75 sx cement. Pulled tubing to 1565' and pumped 110 sx cement. Cement circulated. Pulled tubing out. Topped off casing with 20 sx cement. Backside full of cement.

GPS: 39.41667 -099.80939

Perfs:

Top	Bot	Thru	Comments
3850	3851		
3653	3657		
3566	3569		
3561	3564		

KCC WICHITA
AUG 24 2017
RECEIVED


INVOICED
SEP 01 2017

Remarks: QUALITY CEMENT TICKET # 278

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

AUG 03 2017