

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23364-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 29-7S-22W
1010 feet from N Section Line, 1600 feet from W Section Line
Lease Name: WEBB Well #: 1-29
County: GRAHAM Total Vertical Depth: 3905 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 200 W DOUGLAS AVE #725
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3893		165 SX
SURF	8.625	207		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/27/2017 9:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: ERIK HAGANS Company: VINCENT OIL CORPORATION DBA Phone: (620) 388-5858

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3879' - 3881'.
Port Collar at 1923' w/320 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2017 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3666' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2674' and pumped 75 sx cement. Pulled tubing to 1681' and pumped 110 sx cement. Cement circulated. Pulled tubing out. Topped off casing with 10 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 200 psi.

GPS: 39.42001 -099.80245

Perfs:

Top	Bot	Thru	Comments
3679	3681		


Remarks: QUALITY CEMENT TICKET # 357

Plugged through: TBG

KCC WICHITA
AUG 24 2017
RECEIVED
INVOICED
SEP 01 2017

District: 04

Signed


(TECHNICIAN)

CM

AUG 03 2017