

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23412-00-00
Spot: NESWSENV Sec/Twnshp/Rge: 29-7S-22W
2120 feet from N Section Line, 1730 feet from W Section Line
Lease Name: WEBB Well #: 3-29
County: GRAHAM Total Vertical Depth: 3830 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 200 W DOUGLAS AVE #725
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3827		165 SX
SURF	8.625	209		165 SX
T1	2.375	3780		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2017 9:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: ERIK HAGANS Company: VINCENT OIL CORPORATION DBA Phone: (620) 388-5858

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations at 3665', 3668', 3679' and 3681'.
Port Collar at 1973' w/220 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2017 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3665' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2650' and pumped 75 sx cement. Pulled tubing to 1664' and pumped 115 sx cement. Cement circulated. Pulled tubing out. Topped off with 15 sx cement. Backside full of cement. Shut in pressure 300 psi.
GPS: 39.41698 -099.80207

Perfs:

Top	Bot	Thru	Comments
3679	3681		
3665	3668		

KCC WICHITA
AUG 24 2017
RECEIVED

Remarks: QUALITY CEMENT TICKET # 358

Plugged through: TBG

INVOICED
SEP 01 2017

District: 04

Signed 
(TECHNICIAN) CM

AUG 03 2017