

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19980-00-00
Spot: NWNESENE Sec/Twnshp/Rge: 14-24S-12E
3918 feet from S Section Line, 604 feet from E Section Line
Lease Name: WAYHAM Well #: W-2
County: GREENWOOD Total Vertical Depth: 1736 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1736		100 SX
SURF	8.63	126		65 SX

Well Type: EOR UIC Docket No: E07558.3 Date/Time to Plug: 08/11/2017 10:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Revd. from: DWAIN STOUT Company: Phone: (316) 640-9072

Proposed Plugging Method: Run tubing to TD. Set a 50 ft. cement plug. Pump gel to 1000 ft. Pull tubing and shoot off casing at 1000 ft. Run tubing to 1000 ft. and pump gel to 700 ft. Set a 50 ft. cement plug. and pump gel to 250 ft. Cement from 250 ft. to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL
Date/Time Plugging Completed: 08/15/2017 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran dump baler to 1717' spotted 10 sxs cement, shot casing @ 725' & 250', ran tubing to 725' pumped 20 sxs cement, pulled tubing to 250', pumped 85 sxs cement to surface, gel spacers between cement plugs.

RECEIVED
KCC DIST # 3
AUG 21 2017
CHANUTE, KS

mtt

INVOICED
AUG 30 2017

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



15-073-19980

Cement or Acid Field Report
 Ticket No. **3454**
 Foreman Rick Ledford
 Camp Eureka 12s

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
8-15-17	1046	Wayham W-2				CLW	Ks	
Customer <u>R.R.A Inc.</u>			Safety Meeting		Unit #	Driver	Unit #	Driver
Mailing Address <u>100 S. Main St. Ste 510</u>					102	<u>Rick</u>		
					112	<u>Jason</u>		
					141	<u>Dave</u>		
City <u>Wichita</u>	State <u>Ks</u>	Zip Code <u>67202</u>						

Job Type P.T.A Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8"
 Casing Depth _____ Hole Size _____ Slurry Wt. 14.8" Drill Pipe _____
 Casing Size & Wt. _____ Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting- Rig up to 2 3/8" tubing. Plugging orders as follows:
105'S 1717'
20 SKS @ 72.5'
gel-spacer
85 SKS @ 250' to surface
 "THANK YOU"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	20	Mileage	3.95	79.00
C203	105 SKS	100% permix cement	12.75	1338.75
C206	360"	4% gel	.20	72.00
C206	300"	gel-spacer	.20	60.00
C102A	4.52	ton mileage bulk tax	m/l	345.00
C113	2 1/2 hrs	80 Bbl vac. rate	85.00	212.50
			subtotal	2857.25
			-5% disc.	-153.58
			7.5% Sales Tax	214.29
Authorization by <u>Dwayne Stout</u> Title <u>Co. Lp.</u>			Total	2917.96

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.