

15-009-06629-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 103-1LOCATION SW-SE-SFSEC. 28 TWP. 16 RGE. 12-WDry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease HitchmanOperator Dogier Oil Co Address 1307 N. Math. Bldg. Wichita-Kans.Field _____ County BartonTotal Depth 3370 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 196 ft Circulated with cement
5 1/2 casing set at 3352 ft. 100 sacks of cement
Plugged back to 3340 ft with sand & chat. Dumped
15 sacks of cement at 3340 ft. Shot off & pulled the
5 1/2 casing - run to 250 ft. Set rock bridges &
20 sacks of cement at 250 ft. run to 35 ft.
Plug & 10 sacks of cement at the surface.
The West Supply Co. - Plugging Contractors

RECEIVED
STATE CORPORATION COMMISSION

Q. H. Stough
District Conservation Agent

Date 6-5-53

PLUGGING
FILE SEC 28 T 16 R 12W
BOOK PAGE 103 LINE 1

JUN 18 1953

CONSERVATION DIVISION

Wichita, Kansas

6-8-53