

15-009-07467-00-00

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 76-31

LOCATION Sw-Sw-NW

SEC. 28 TWP. 16 RGE. 12 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Landick "A"

Operator Derby Drly. Co. Address 352 N. Broadway, Wichita Ks.

Field \_\_\_\_\_ County Barton

Total Depth 3397 Feet.

Plugging Contractor West Supply Co., Inc.

Plugging Contractor's License No. \_\_\_\_\_

Address Chase Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 1/2" @ 225' C.W.C. 5 1/2" set 3382'  
4 1/2" at Cem. Plugged back to 3350' Top Perf. 3168'  
Sand to 3160' dumped 5 at Cem. Shot off and  
pulled 5 1/2" casing. Mudded hole to 225'  
Set rock bridge and run 25 at Cem. mud to  
35' rock bridge and 10 at Cem to base of  
cellar

RECEIVED  
STATE CORPORATION COMMISSION

DEC 8 1954

CONSERVATION DIVISION  
Wichita, Kansas

Warren H. Horner  
District Conservation Agent

Date Dec 3, 1954

12-8-54

PLUGGING  
FILE SEC. 28 TWP. 16 R 12 W  
BOOK PAGE 26 LINE 51