


15-185-12998-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1072
CONSERVATION DIVISION
Wichita, Kansas
11-9-72

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Wichita Iron & Metals Corp

Complete Address Box 13021 Wichita, Ks

Lease Name Robl Well No. 1-?

Location NW/NE Sec. 2 Twp. 21 Rge. 12 (E) (W)

County Stafford Total Depth 3430

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address 204 E 6th Ellinwood, Ks License No. 396

Operation Completed: Hour 9:00 AM Day 7 Month 11 Year 1972

The above well was plugged as follows:

300 ft 10 3/4 surface cement circulated. 3425 ft 7" long string

cemented with 100 sacks. Open hole. Sand to 3000 ft, 7 sacks cement

with bailer. Pulled 2500 ft 7". Pump 3 sacks hulls, 20 sacks gel,

100 sacks cement to surface.

Pumped by Allied Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11/9/72
INV. NO. 6602-W