

15.185.19505.0001

Form CP-3  
Rev. 6-26-62

4  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUN 22 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name F. G. Holl

Complete Address: 6427 East Kellogg, Wichita, Kansas

Lease Name Copeland Well No. # 1

Location NE SE NE Sec. 2 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3425

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Manning Drilling Company

Address: Box 96, Ellinwood, Kansas License No. 386

Operation Completed: Hour 3:30PM Day 19th Month June Year 1964

The Above well was plugged as follows:

284' of 8 5/8" surface pipe, cemented with 205 sacks. 3425' of 4 1/2" long  
string, cemented with 75 sacks. Top perferation 3348'. Bottom of the  
hole was sanded to 3330'. and cemented with 3 sacks. Fluid in hole was  
bailed down to 275', plug was set on fluid at 275, and 10' of rock  
bridge, cemented with 25 sacks. Hole was filled with mud to 40', with  
10' of rock bridge, and cemented with 10 sacks to base of the cellar.  
2700' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/23/64

INV. NO. 9338-U

Signed: Archie Elving  
Well Plugging Supervisor