

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1962  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Amarillo Oil Co.

Complete Address: Box 151 Amarillo, Texas

Lease Name C.F. Wright Well No. 7

Location C SE NE Sec. 33 Twp. 27S Rge. (E) 34(W)

County Finney Total Depth 4860

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Garvey Drilling Co. And Toms Well Service

Address: Wichita, Kansas Garden City, Kansas License No.     

Operation Completed: Hour 2:00AM Day 11 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 402' cir.w/cement. 4 1/2" 4439' cem.w/120 sax. Bridge at 4210!  
Heavy mud 4210' to 4050' Cem. w/10 sax. and plug 4050' to 3950'  
Heavy mud 3950' to 450' Cem.w/50 sax. and plug 450' to 350'  
Heavy mud 350' to 40' Cem.w/15 sax. and plug to top.  
Cap weld on top. (Halliburton Cem. Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/16/62

INV. NO. 5363-W

Signed: Hughes  
Well Plugging Supervisor