

15-009-00895-00-00



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1975

CONSERVATION DIVISION
Wichita, Kansas

6-10-1975

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Four Way Operating, Inc

Complete Address P.O. Box 698 Great Bend, Kansas 67530

Lease Name Klug Well No. 1

Location SESE SW Sec 31 Twp. 16 Rge. 12 (W) X

County Russell Total Depth 3438

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Inc - Allied Cem.

Address P.O. Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 4:30 PM Day 6 Month 6 Year 1975

The above well was plugged as follows:

Sand to 3050' & 5sx Cement @ Dump Baler - Squeezed thru.

8 5/8" @ 3sx Halls - 10sx Mudgel - 1sx Halls & 100sx Cement

Max Pressure 1100# - Shut in Pressure 700#

Plugged Back to 3400' Top Perf. @ 3177

3424' of 5 1/2" casing - Cemented @ 125sx Cement

157' of 8 5/8" surface casing cemented @ 100sx Cement

Recovered 1869' 5 1/2" casing

I hereby certify that the above well was plugged as herein stated.

Signed: Duane Rankin
Well Plugging Supervisor

INVOICED

DATE 6/13/75

INV. NO. 1466-W