



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 35-37

LOCATION SW-SE-NW

SEC. 31 TWP. 16 RGE. 12W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Klug

Operator Walt Cook Refr-TM Address 820 Union Natl Bank Bldg. Wichita

Field _____ County Barton

Total Depth 3450 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 2450 - Circulated with Cement
5/8 casing set at 3432ft - Plugged back down bottom
to 3330ft - Rock bridge & 5 sacks of cement at 3330ft -
Shut off & Pulled 2850ft & 5/8 casing - Filled with
 mud to 240ft - Bridge & 15 sacks of cement - Filled
to 30ft - Plug & 10 sacks of cement -
Bill Baglik - Pipe Pulling - Contractor

C. M. Stoughton
District Conservation Agent

Date 7-24-48

PLUGGING
FILE SEC 31-16-12W
BOOK PAGE 35 LINE 37

7-27-48