

15.185.01930.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Co
Complete Address 217 N Water Wichita, KS
Lease Name E Siefkes Well No. 3
Location SW/SW/SE Sec. 34 Twp. 21 Rge. 12 (E) (W) W
County Stafford Total Depth 3632
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Co Inc
Address Box 405 Chase, KS License No. 436
Operation Completed: Hour 11:00 AM Day 2 Month 3 Year 1973

The above well was plugged as follows:

252 ft 10 3/4 surface cemented with 250 sacks. 3620 ft 7" long string
cemented with 100 sacks. Top perf. 3361 ft. Sand to 3350 ft, 7 sacks
cement with bailer. Pulled 1600 ft 7". Set 10 ft rock bridge at
200 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 3/5/73
INV. NO. 7092-w