

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Duke Drilling Company

Complete Address: P. O. Box 823, Great Bend, Kansas

Lease Name Hall Well No. # 1

Location C W/2 SE NE Sec. 12 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3500

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:30AM Day 16th Month Nov. Year 1964

The Above well was plugged as follows:

283' of 8 5/8" surface pipe, cemented with 200 sacks. 3497' of 5 1/2" long
string, cemented with 100 sacks. Top perforation 3430'. Bottom of the
hole was sanded to 3400', and cemented with 5 sacks. Hole was full of
fluid. Bridge plug was pushed in fluid to 260', and 10' of rock bridge
on plug. 10 sacks of cement was mixed in barrel, and put on plug at 250',
through the dump bailer. And let set over night. Next morning hole was
bailed dry, and 15 sacks' of cement was added to the plug. Hole was filled
with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the
base of the cellar. 2515' of 5 1/2" long string was recovered from the hole.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/18/64

INV. NO. 184-W