

15.185.30387.0000

Form CP-3
Rev. 6-26-62

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 7 1966

CONSERVATION DIVISION
STATE CORPORATION COMMISSION

11-18-1966

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Duke Drilling Company

Complete Address: P. O. Box 823, Great Bend, Kansas

Lease Name Hall Well No. # 2

Location SW NE NE Sec. 12 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3500'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:30AM Day 17th Month Nov. Year 1966

The Above well was plugged as follows:

281' of 8 5/8" surface pipe, cemented with 325 sacks. 3500' of 4 1/2" long
string, cemented with 75 sacks. Plug back T.D. 3447'. Top perferation
3430'. Bottom of the hole was sanded to 3300', and cemented with 4 sacks,
through the dump bailer. 2750' of 4 1/2" long string was recovered from the
hole. Bridge plug was pushed in fluid to 275', rock bridge from 275' to
260'. 10 sacks of cement was mixed in a barrel, and put on plug at 260',
through the dump bailer, and let set for two days. Hole was bailed dry,
and 15 sacks of cement was added to the plug. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elwing
Well Plugging Supervisor

DATE 11/18/66
INV. NO. 4305-11