


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 2 Twp 21 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines NE - NW - NW
Lease Owner Meltzer Oil Company
Lease Name Hewitt Well No. 2
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4-5 1960
Plugging completed 4-8 1960
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	254	None
				5 1/2	3426	2962.09

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 3190' - dumped 5 sacks of cement - bailed fluid to 240' - filled with mud to 240' - set 10' rock bridge and dumped 15 sacks of cement - mudded to 40' - set rock bridge - dumped 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 154 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Nathan Meltzer

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan Meltzer
Box 191, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of April, 1960

My commission expires 3/30/61

Anne Meltzer
Anne Meltzer Notary Public.

15.185.12996.0000

D R I L L E R ' S L O G

COMPANY: THE LOTUS OIL COMPANY

LOCATION: NE NW NW 2-21-12
Stafford County, Kansas

CONTRACTOR: HILTON DRILLING COMPANY, INC.

ELEVATION: 1840 DF

FARM NAME: HEWITT NO. 2

COMMENCED: 12-2-51

COMPLETED: 12-15-51

CASING USED: 8-5/8" at 254' with 250 sacks
5-1/2" at 3426 1/2' with 75 sacks

Sand, Clay	41
Sand	85
Sand	225
Red Bed	254
Red Bed and Shells	605
Anhydrite	635
Shale, Shells	975
Shale, Shells, Salt	1210
Shale, Salt, Shells	1400
Shale and Lime	1460
Broken Lime	1900
Lime and Shale	2390
Shale, Shells	2540
Shale and Lime	2775
Lime	3087
Lime, Shells and Shale	3169
Lime	3428
Total Depth	3428

RECEIVED
 STATE CORPORATION COMMISSION
 APR 4 1960
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

Henry Pearson
 Secretary

Subscribed and sworn to before me this 19th day of December, 1951.

Edwina Elder
 Notary Public

My commission expires September 21, 1953.