


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 2 Twp. 21 Rge. 12 ~~XXX~~ W(W)

Location as "NE/CNW%SW%" or footage from lines C NE/4 NW/4 SE/4
Lease Owner Stanolind Oil and Gas Company
Lease Name Anna Robl "B" Well No. 1
Office Address P. O. Box 1654, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-19-19 55
Application for plugging filed (Verbal) 7-19-19 55
Application for plugging approved 7-19-19 55
Plugging commenced 7-19-19 55
Plugging completed 7-19-19 55
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production --- 19 ---
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well S. S. Greider
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	Dry	3177	3395	8-5/8	600	None
Arbuckle	Salt Water	3435	3440			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

- Hvy Rotary Mud 3440-600
- Wood Plug 600-598
- 15 Sx. Cement 598-550
- Hvy Mud 550-30
- 10 Sx. Cement 30- To Bottom of Celler

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barbour Drilling Company 7-23-1955
Address Tulsa, Oklahoma

STATE OF KANSAS COUNTY OF BARTON ss.
I. G. A. Reynolds (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. G. A. Reynolds
P. O. Box 7, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of July, 19 55

My commission expires November 12, 1958 W. Daugherty Notary Public.

PLUGGING
FILE SEC 2 T 21 R 12W
BOOK PAGE 135 LINE 28

FORMATION RECORD

DESCRIBE EACH FORMATION DRILLED. INDICATE THICKNESS, CONTENT AND WHETHER DRY, OR OIL, GAS, OR WATER BEARING.

FORMATION	TOP	BOTTOM	FORMATION	TOP	BOTTOM
Sand, Clay	0	200			
Red Bed, Shale	200	300			
Red Bed, Sand	300	598			
Anhydrite	598	617			
Shale, Shells	617	1525			
Shale, Lime	1525	2280			
Shale	2280	2515			
Shale, Lime	2515	2980			
Lime	2980	3060			
Lime, Shale	3060	3177			
Lensing Top	3177				
Lime	3177	3405			
Lime, Shale	3405	3415			
Shale	3415	3435			
Arbuckle Top	3435				
Lime, Salt Water	3435	3440			
Run Schlumberger Electric Logs to T.O.					
Total Depth					
By Schlumberger		3438			
By Rotary Drill		3440			
Well Plugged and Abandoned					
7-19-55					

STANOLIND OIL AND GAS COMPANY

15-185-00984.0000

CENTRAL DIVISION

CE N° 35537

FIELD PURCHASE ORDER

Mant

DATE July 19, 1955

ORDERED FROM State Corporation Commission

ADDRESS 911 N. Broadway Wichita, Kansas
 RENDER INVOICE IN DUPLICATE FOR EACH ORDER, SHOW ORDER NUMBER ON ALL COPIES OF INVOICE AND MAIL TO

STANOLIND OIL AND GAS COMPANY Box 7 E. Lawrence, Kansas
 CITY STATE

DELIVER MATERIAL TO _____

QUANTITY	DESCRIPTION	FEA	SYM	UNIT PRICE	AMOUNT
	<i>Plugging Fee</i>				

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 20 1955
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 PAGE SEC-2 T-21 P. 12W
 PAGE 125 LINE 28

CHARGE TO Anna Rohl R#1

USED FOR _____

- ORIG. OR CHNG. CONST. OPERATIONS OR REPAIRS
- REPLACEMENT
- POSTED TO _____

TERMS
 BY ACCEPTANCE OF THIS ORDER SELLER OR CONTRACTOR AGREES TO AND SHALL BE BOUND BY THE TERMS AND CONDITIONS PRINTED ON THE BACK HEREOF.

STANOLIND OIL AND GAS COMPANY

By *A. K. ...*

SELLER

- No. 1. This order is given on the express condition and agreement that the Seller, its heirs, successors, assigns and legal representatives, shall forever protect, indemnify and save harmless the Buyer against any and all claims, suits in law or equity, judgments, court costs, attorneys' fees, and other liabilities, demands or losses in any manner arising out of alleged infringement of any patent, copyright and trade mark rights because of the possession, use or sale by the Buyer or its agents of the subject matter to which this agreement relates, it being understood that said Buyer will promptly notify said Seller of the bringing of said suits, and that Seller shall have the right to be represented in the defense thereof by counsel of its own selection and at its own expense; it is further of the essence of this agreement and a part of the consideration for entering into it by the Buyer that the Buyer shall have a free and unrestricted right and license to use said subject matter in any and all ways and under all patents in or under which Seller may now or hereafter have an interest.
- No. 2. In the event Buyer and Seller have heretofore entered into a written agreement providing for the purchase and sale of the products mentioned in this order and the period covered by such prior agreement has not expired, then this order shall be considered as made by Buyer and accepted by Seller on the same terms and conditions set forth in said prior agreement and nothing herein contained shall be held in any manner to be a modification of such prior agreement of purchase.
- No. 3. Seller represents that the sale of the article or articles referred to herein, and the price therefor and delivery thereof will conform to all applicable federal and state laws, orders, rules and regulations.

CONTRACTOR

By acceptance of this order contractor agrees that in the performance of the above work, contractor shall act solely as an independent contractor and as such is solely responsible for all contributions and taxes imposed under unemployment compensation or insurance laws covering employees of contractor. Contractor guarantees that all material sold and delivered hereunder has been or will be produced, and all work, labor and services performed hereunder has been or will be performed and prices therefor have been or will be charged in strict accordance with all applicable state and federal laws, rules, regulations and orders.