

WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Stafford County. Sec. 2 Twp. 21 Rge. 12(W)

Location as "NE1/4NW1/4SW1/4" or footage from lines SW SW NE

Lease Owner The Bay Petroleum Corporation

Lease Name Robl Well No. 1

Office Address Box 957, Denver, Colorado.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June, 6, 19 48

Application for plugging filed June, 6, 19 48

Application for plugging approved June, 6, 19 48

Plugging commenced June, 6, 19 48

Plugging completed June, 6, 19 48

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C.D. Stough

Producing formation Arbuckle Test Depth to top 3470 Bottom Total Depth of Well 3512 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8 5/8", 315', None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

June, 6, 1948 - 15 sax cement on bottom of hole, Filled hole w/heavy mud to 200', Set plug at 200', 10 sax cement on top of plug, 25' below top of surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Bay Petroleum Corporation Box 513, Chase Kansas.

STATE OF Kansas COUNTY OF Rice ss. Forrest Crawford (employee of owner) or former owner of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Handwritten Signature]

(Address)

SUBSCRIBED AND SWORN to before me this 8 th day of June 19 48

My commission expires May, 20, 1950

Curran O. Gray Notary Public.



ROBL NO. 1 WELL

Location: C. SW/4 SW/4 NE/4
 Sec. 2-21S, R12W
 Stafford County, Kansas

Date Spudded: 5-27-48

Total Depth: 3512'

Operator: Bay Petroleum Corporation

Elevation: 1830' DF

Contractor: Birmingham-Bartlett Drilling Co.

Top Arbuckle: 3470'

Casing Record: 16 jts., 320' Of 8-5/8" 28#
 casing cemented at 315' with
 200 sax bulk cement. 2 CC

Oil String None run
 Dry# and Abandoned, June, 6, 1948

LOG

(Figures indicate Bottom of Formation)

0 to 95 sand and clay	2255 lime and shale
225 shale and shells	2600 shale and shells
582 red bed and shells	2695 lime and shale
607 anhydrite	2825 shale and shells
1010 shale and shells	2965 shale and lime
1060 shale and salt	3085 lime
1200 salt	3120 shale
1400 shale and shells	3215 lime and shale
1710 broken lime	3434 lime
1840 lime	3475 shale
1900 broken lime	3512 shale and lime
2095 shale and shells	

The undersigned, RICHARD HINDERER, of the BIRMINGHAM-BARTLETT, DRILLING CO., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

BIRMINGHAM-BARTLETT DRILLING CO.,

By S/ Richard Hindery

Subscribed and sworn to before me
 this 9th day of June, 1948

S/ Vivian F. Yinger
 Notary Public

My commission expires: November, 29, 1950

