


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec 2 Twp. 21 Rge. 12 (E) (W)
Location as "NE/CNW&SW" or footage from lines SW NE NE
Lease Owner Specter Pipe & Supply, Inc.
Lease Name Anna Robl Well No. 3
Office Address Box 169, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-18-54 19
Application for plugging filed 1-15-69 19
Application for plugging approved 1-16-69 19
Plugging commenced 2-3 19 69
Plugging completed 2-7 19 69
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation arbuckle Depth to top 3404' Bottom 3404' Total Depth of Well 3408 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	272'	none
				5 1/2"	3404'	2327.50'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3100' with sand
Dumped 5 sacks cement
Set rock bridge at 260'
Dumped 25 sacks cement
Mudded hole to 40'
Set rock bridge at 40'
Dumped 10 sacks cement to top.

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Lynch
Address Rt 4 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Russell, ss.
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of February, 1969

My commission expires May 21, 1971

Wilma M. Lindahl
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15.185.13142.0000


COPY

Company. STANOLIND OIL & GAS CO.
Farm. Anna Robl No. 3

SEC. 2 T. 21 R.12W.
SW NE NE
990' S of NL, 990' W of EL

Total Depth. 3408
Comm. 7-9-54 Comp. 7-18-54
Shot or Treated.
Contractor.
Issued. 9-18-54

County Stafford
KANSAS



Elevation. 1829 BB

Production. 163 bbls.

CASING:

8 5/8 @ 272' w/ 300 sx cmt.
5 1/2 @ 3404' w/ 150 sx cmt.

Figures Indicate Bottom of Formations.

sand & gravel	236
red bed	590
anhydrite	615
shale & shells	1750
lime & shale	1815
lime	1918
lime & shale	3223
lime, oil shows	3408
Total Depth	

TOPS:
Lansing 3153
Arbuckle 3404

Ran Schlumberger electric logs to TD. Schlumberger TD 3404

Cored 3395-3405: rec 5' 5" green shale

Cored 3400-3405: rec. 1-1/2' green shale
1' dolo. lime w/ shale streaks,
bleeding oil in spots

Cored 3405-3408: rec, 1-1/2/3
1-1/2 dolo. lime, good porosity, bleed-
ing oil

Bailed, drilled plug, cleaned out
to TD.

Swab off bottom 8 hr test: 6.72 BOPH
Indicated pot. by swab 163 BOPD

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1969
CONSERVATION DIVISION
Wichita, Kansas