


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County, Sec. 2 Twp. 21S Rge. 11W E/W  
Location as "NE/CNW/SW" or footage from lines  
C SL, SW/4

Lease Owner F. G. Holl  
Lease Name Ragan "E" #2 Well No. 2  
Office Address 6427 East Kellogg, Wichita, Kansas 67207  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Dry Hole  
Date Well completed August 7, 1979 19  
Application for plugging filed August 12, 1979 19  
Application for plugging approved August 12, 1979 19  
Plugging commenced 3:00 PM, August 12, 1979 19  
Plugging completed 4:45 PM, August 12, 1979 19  
Reason for abandonment of well or producing formation

Dry Hole  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3440'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	254'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
Pumped thru open D.P. 40 sacks 50/50 Pozmix  
with 1% gel at 450' and 25 sacks at 240'  
solid bridge at 40' with plug and 1/4 sack  
hulls and 10 sacks to surface.  
2 sacks in rathole.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 29 1979

(If additional description is necessary, use BACK of this \_\_\_\_\_)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner  
STERLING DRILLING COMPANY  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1979

CHARLES M. HALL  
Notary Public  
Rice County, Ks.  
My App. Exp. Jan. 31, 1982

Charles M. Hall, Notary Public.

My commission expires

15.185-20941.0000

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- RUCAL "E" #2  
Located: C 2L, SW/4, Section 2-210-111, Stafford County,  
Kansas

OWNER: P. C. Noll  
ROTARY DRILLING OPERATOR: Sterling Drilling Company

DATE STARTED: August 7, 1979  
DATE STOP: August 12, 1979

TOTAL DEPTH: 3440'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 150 Sand	Ran 7 joints used 2 3/4", 8 5/8" casing, 241.62' set at 254' K.B. with 225 sacks 60/40 Pozmix with 37 cc. Plug down at 11:00 PM, 8-7-79, by Rowco.
150 - 256 Shale	
256 - 1050 Red Bed and Salt Shale	
1050 - 3285 Lime and shale	
3285 - 3375 Lime, shale, Chert	
3375 - 3440 Lime, shale, sand	
	Plugged.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 29 1979

CONSERVATION DIVISION  
Wichita, Kansas