


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 2 Twp. 21 Rge. 11 (#) W (W)
Location as "NE/CNW/SW" or footage from lines NW SE NE
Lease Owner F. G. Holl
Lease Name Copeland Well No. 1
Office Address 6427 East Kellog, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 11th 19 62
Application for plugging filed " " 19 62
Application for plugging approved " " 19 62
Plugging commenced August 11, 19 62
Plugging completed August 11, 19 62
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. W. L. Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3423 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 200 ft.
Set wooden plug at 200', 1/2 Sacks Hulls & 20 Sacks Cement.
Filled hole with heavy mud to 35 ft.
Set wooden plug with 1/4 sks. hulls & 10 sacks cement @ 35ft.
Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Company
Address P.O. Box 823, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
L. O. Chubb (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P.O. Box 823, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of August, 19 62

My commission expires 3-1-66

[Signature]
Shirley V. Maier Notary Public.

W E L L L O G

Date Commenced: August 3, 1962
 Date Completed: August 11, 1962

F. G. Holl
 COPELAND #1
 NW SE NE
 Section 2-21-11w
 Stafford County, Kansas

0 - 50 Surface Sand
 50 - 185 Sand & Clay
 185 - 462 Red Bed
 462 - 475 ANHYDRITE
 475 - 733 Red Bed
 733 - 1095 Shale & Shells
 1095 - 1190 Salt & Shale
 1190 - 1445 Shale & Shells
 1445 - 2110 Shale & Lime
 2110 - 2500 Shale & Shells
 2500 - 2811 Lime - Shale
 2811 - 2920 Lime
 2920 - 2938 Shale Lime HEEBNER
 2938 - 2952 Lime TORONTO
 2952 - 3050 Shale DOUGLAS
 3050 - 3072 Lime Shale BROWN LIME
 3072 - 3330 Lime LANSING
 3330 - 3060 CONGLOMERATE
 3060 - 3394 Shale SIMPSON
 3394 - 3423 Dolomite ARBUCKLE

ELEVATION 1763 K.B.

FORMATIONS
 Heebner 2920
 Brown Lime 3050
 Lansing 3072
 Conglomerate 3330
 Simpson 3360
 Arbuckle 3394
 R.T.D. 3423

SURFACE CASING: Set 286' of
 8-5/8" casing at 284' with
 225 sacks cement.

A F F I D A V I T

RECEIVED
 STATE CORPORATION COMMISSION

AUG 22 1962

STATE OF KANSAS
 COUNTY OF BARTON) ss.

CONSERVATION DIVISION
 Wichita, Kansas

L. O. Chubb, of lawful age, does swear that the facts
 and statements herein contained are true and correct to the best of
 his knowledge,

L. O. Chubb
 L. O. Chubb

Subscribed and sworn to before me this 21st day of August, 1962

Shirley V. Maier
 Shirley V. Maier-NOTARY PUBLIC

My Commission Expires:
 March 1, 1966