

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Finney County, Sec. 33 Twp. 21S Rge. 34 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines C SE/4 NE/4
Lease Owner C. F. Wright
Lease Name C. F. Wright Well No. 1
Office Address P. O. Box 151
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 7/9/62 19
Application for plugging filed 7/11/62 19
Application for plugging approved 7/10/62 (verbal) 19
Plugging commenced 7/10/62 19
Plugging completed 7/10/62 19
Reason for abandonment of well or producing formation No production

NORTH

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4860 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing - K.C. Ls.	Water	4100	4110	8-5/8	402	None
Upper Marmaton Ls.	Oil & Water	4307	4312	4-1/2	4439	3565
Lower Marmaton Ls.	Oil & Water	4324	4330			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4 1/2" casing was set on this well at a depth of 4439'. Using Halliburton equipment, a cement plug was spotted from 3950 to 4050'.

4 1/2" casing was shot off @ 3565' and pulled. A 45 sx. cement plug was spotted thru tubing from 350' to 450' and a 15 sack plug was spotted from 0 to approx. 40'. A steel plate was welded over the top of the 8-5/8" surface casing.

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Company
Address Liberal, Kansas

STATE OF Texas COUNTY OF Potter, ss.
J. A. Tipton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Tipton J. A. Tipton
P. O. Box 151, Amarillo, Texas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of July, 1962

My commission expires June 1, 1963

Georgia J. Weathers
(Georgia J. Weathers) Notary Public.
Potter County, Texas

WELL LOG

Company: Amarillo Oil Company
 Farm: C. F. Wright No.: 1
 Total Depth: 4860
 Comm.: 6-4-62 Comp.: 7-9-62
 Contractor: Garvey Drilling Company

Sec. 33 T. 21S R. 34W
 Loc.: C SE/4 NE/4
 County: Finney

Casing: 8-5/8" -- (Put in) 402', (Took out) None
 4-1/2" -- (Put in) 4439', (Took out) 3565'

Elevation: 2961 GL
 2968 KB
 Production: None

"Figures Indicate Bottom of Formations"

0 - 400	Surf. sd., shale
400- 725	Shale, sd.
725- 950	Salt, shale, anhy.
950- 1350	Sd, salt, shale, anhy.
1350- 1535	Anhy, salt
1535- 2345	Shale, salt, anhy, shale
2345- 2500	Anhy, ls
2500- 3060	Ls, shale
3060- 3630	Ls, w/shale strks.
3630- 4275	Ls, cherty ls., shale brks.
4275- 4635	Cherty ls, shale
4635- 4725	Shale
4725-4860	Ls w/shale strks.

DrLr's. T. D. - 4860'

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 13 1962
 CONSERVATION DIVISION
 Wichita, Kansas

State of Texas)
 County of Potter) ss

I, Stanley F. Gray of Amarillo Oil Company

upon oath state the above and foregoing is a true and correct copy of the log of the
C. F. Wright #1 well.

Stanley F. Gray

Subscribed and sworn to before me this 11 day of July, 19 62

My Commission Expires: June 1, 1963

Georgia J. Weathers
 (Georgia J. Weathers)
 Notary Public
 Potter County, Texas