

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to:

Conservation Division State Corporation Commission 800 Biting Building Wichita, Kansas

Stafford County. Sec. 34 Twp 21 Rge. 12 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines 330' from S L, 660 E.L

Lease Owner Harry Woodring and Thurman Hill

Lease Name Siefkes Well No. 1

Office Address Topeka, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole) Dry

Date, well completed 9/5/40 193

Application for plugging filed 9/5/40 193

Application for plugging approved 9/5/40 193

Plugging Commenced 9/5/40 193

Plugging Completed 9/5/40 193

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 193

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation Depth to top Bottom Total Depth of Well 3764 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 10-3/4", 155', 0

Describe in detail the methods used in which the well was plugged... STAFFORD COUNTY

Filled from bottom to 155' with heavy rotary mud. Wooden plug, 8 sacks cement to 140'. Extra heavy mud to 15'. 7 sacks of cement on surface pipe sealed and welded and capped.

PLUGGING FILE 34 21 12W BOOK PAGE 15 LINE 27 9-9-1940

SEP 9 1940 STATE CORP. COMM CONSERV. DIV.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Schneider-Pulse 301 Hoke Building, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss. CLYDE PULSE

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Hutchinson, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 6th day of September, 1940

My commission expires June 13, 1942

[Signature]

Notary Public

LOG: Sit. #1, SW/4, KANS.


OWNER: H. WOODRING, ETAL

DRILLERS: SCHNEIDER-PULSE, 301 HOKE BUILDING, HUTCHINSON, KANSAS.

COMMENCED: AUGUST 18, 1940 COMPLETED: SEPTEMBER 6, 1940

15.185.61650.0000

Surface and Sand	60'
Sand	140
Hard Sand	185
Red Beds	625
Anhydrite	670
Shale and Shells	1470
Shale	1500
Lime	1625
Lime and Shale	1695
Broken Lime	1722
Broken Lime	1885
Lime and Shale	2210
Shale	2280
Shale and Lime	2345
Shale	2595
Lime	2645
Lime and Shale	2725
Shale	2840
Lime (Topeka)	3140
Shale	3270
Lime and Shale	3285
Lime (K. C.)	3550
Shale and Shells	3560
Shale	3620
Conglomerate	3654
Chert	3710
Green Shale	3760
Siliceous Lime	3764



T. D. - D and A

- - -CASING RECORD- - -

155' of 10-3/4" casing, Cemented 185 sacks.

PULSE

I, CLYDE PULSE, Manager of The Schneider, do hereby certify that this is a true and correct log of the formation encountered on the above mentioned well as taken from the daily drilling reports thereof.

SIGNED

Clyde Pulse
Manager.

SUBSCRIBED and SWORN TO BEFORE ME
THIS 6th DAY OF September 1940

B. Alice Smith
Notary Public

My Commission Expires June 13, 1942