

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

SEP 10 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name F. G. Holl

Complete Address: 6427 E. Kellogg, Wichita, Kansas

Lease Name W. A. Rugan "D" Well No. # 3

Location NE SW NE Sec. 2 Twp. 21 Rge. 11 (E) W

County Stafford Total Depth 3386'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Manning Drilling Company

Address: Box 96, Ellinwood, Kansas License No. 386

Operation Completed: Hour 2:00 PM Day 4th Month Sept. Year 1965

The Above well was plugged as follows:

274' of 8 5/8" surface pipe, cemented with 225 sacks. 3377' of 4 1/2" long
string, cemented with 75 sacks. This is an open hole. Bottom of the hole
was sanded to 3360', and cemented with 3 sacks. 2740' of 4 1/2" long string
was recovered from the hole. Fluid in the hole was at 200', bridge plug
set on fluid at 200', rock bridge from 200' to 190', and cemented with
25 sacks. Hole was filled with mud to 40', rock bridge from 40' to 30',
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/10/65

INV. NO. 1778-W