

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Duke C. Burt of Burt Drilling Company has this
date requested permission to plug the following described well:

Mr. Robert C. Brooks guarantees payment of the plugging fee.

Operator's full Name: Robert G. Brooks

Complete Address: 102 C. Insurance Bldg., Wichita, Kansas

Lease Name: Reif Well No. # 1

Location: NW SW SW Sec. 30 Twp. 16 Rge. 12 (E)(W) W

County Barton Total Depth 3420 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Duke C. Burt was instructed to plug the well as follows:

8 5/8" 310' Cwc.

Circulated hole with heavy mud to 425', set plug, & displaced 25 sax

cement thru drill pipe. Mud to 300', set plug, & displaced 25 sax

cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced

10 sax cement, cementing to base of cellar.

Very truly yours,

Don Linn
Conservation Division Agent