


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 34 Twp. 21 Rge. 12 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
W/2-NE-NW
Lease Owner Woodman - Iannitti Drilling Company
Lease Name Williamson Well No. 2
Office Address Box 308, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced January 24 19 78
Plugging completed January 30 19 78
Reason for abandonment of well or producing formation
Depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 3647'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	285'	None
				5 1/2"	3634'	2,674.25'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped sand to 3600' and 5 sacks cement.
Shot pipe at 3000', 2910', 2800' and 2710'.
Pulled 85 joints 5 1/2" casing.
Plugged well with 3 sacks hulls, 20 sacks gel, 100 sacks cement 3% gel and 3% calcium chloride.

RECEIVED
STATE CORPORATION COMMISSION
2-1-1978
FEB 01 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
Box 698 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
Box 698, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of January, 1978

My commission expires

STATE NOTARY PUBLIC
ANITA L. BOGLE
Barton County, Kansas
My Appt. Exp. Nov 21, 1981

Anita L. Bogle
Notary Public.

K. T. WOODMAN
REG. PHONE 733-0418
C.F. PHONE 265-7650
WICHITA, KANSAS

JAN 23 1978
D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

15.185.20763.0000

1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

August 30, 1977

Company;	Woodman & Iannitti Drilling Co.
Farm;	#2 Williamson
Location;	C W/2 NE NW
Section;	34-21-12W
County;	Stafford
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	August 18, 1977
Compl;	August 27, 1977
Total Depth;	3647
Casing;	8 5/8 @ 285 w/225 sx. 5 1/2 @ 3634 w/100 sx.

Figures Indicate Bottom Of Formations:

40	Sand & clay
285	Shale
645	Shale & red bed
660	Anhy
1005	Shale
1725	Shale
1940	Shale & Lime
2325	Lime
2530	Lime
2805	Lime & shale
2965	Lime & shale
3180	Lime
3425	Lime
3615	Lime
3647	Lime

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman

RECEIVED
STATE CORPORATION COMMISSION

JAN 24 1978

CONSERVATION DIVISION
Wichita, Kansas