

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-22,769-0000

LEASE NAME Osborne

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 2

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 12 TWP. 21 RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed 4-24-91

Plugging Commenced 4-24-91

Plugging Completed 4-24-91

LEASE OPERATOR Eldon J. Schierling

ADDRESS 333 East English - Suite 240 Wichita, KS 67202

PHONE# (316) 267-0042 OPERATORS LICENSE NO. 7916

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-22-91 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? to be filed
 by operator if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put In	Pulled out

STATE CORPORATION COMMISSION
 APR 29 1991
 CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Bottom Plug: @ 3475' w/40 sacks cement thru drill pipe
 Next Plug: @ 620' w/50 " " " " " 15 sacks in Rat Hole
 Next Plug: @ 350' w/50 " " " " " fill up water well w/cement
 Top Plug: @ 40' w/10 " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Eldon J. Schierling

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson


(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 26th day of April, 19 91



My Commission Expires _____

Paula Ann Laudick
 Notary Public

DRILLER'S WELL LOG

DATE COMMENCED: April 19, 1991
DATE COMPLETED: April 24, 1991

Eldon J. Schierling
OSBORNE #2
NE SE SE
Sec. 12, T21s, R12W
Stafford County, Ks.

0 - 188' Surface Soil, Sand
188 - 590' Sand & Red Bed
590 - 613' Anhydrite
613 - 2010' Shale & Lime Streaks
2010 - 2763' Lime & Shale
2763 - 3051' Lime
3051 - 3085' Shale & Lime
3085 - 3176' Shale
3176 - 3196' Lime & Shale
3196 - 3437' Lime
3437 - 3452' Shale & Lime
3452 - 3500' Sand & Shale
3500 - 3600' Dolomite
3600' RTD

ELEVATION: 11829' K.B.

Surface Pipe: Set new
8-5/8", 20# pipe @309'
w/200 sacks 60/40pozmix
2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) SS

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 26th day of April 1991.



Paula Ann Laudick
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

APR 29 1991

CONSERVATION DIVISION
Wichita, Kansas