


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 33 Twp. 22²¹ Rge. 12 (W) (W)
Location as "NE/CNW%SW%" or footage from lines. NE SW SW
Lease Owner Meltzer Oil Company
Lease Name "Walker" Well No. 2
Office Address P.O. Drawer "B", Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 10, 1962 19
Application for plugging filed " 19
Application for plugging approved 19
Plugging commenced March 10, 19 62
Plugging completed " 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. L. Lackamp
Producing formation Depth to top Bottom Total Depth of Well 3639 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 400 feet.
Set wooden plug 1/4 sack hulls and 20 sacks cement
Filled hole with heavy mud to 260 feet.
Set wooden plug 1/2 sack hulls and 20 sacks cement.
Filled hole with heavy mud to 35 feet, set plug 1/4 sack hulls and 10 sacks cement.
Plugged rat hole.

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.
Address P.O. Box 823, Great Bend, Ks.

STATE OF KANSAS, COUNTY OF BARTON, ss.
Lewis O. Chubb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lewis O. Chubb
P.O. Box 823, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12 day of March, 19 62

My commission expires 6-24-63. Clair E. Stinson Notary Public.



DRILLER'S WELL LOG

Date Commenced: March 2, 1962
Date Completed: March 10, 1962

MELTZER OIL COMPANY
Walker # 2
NE/4 SW/4 SW/4 21
Section-33-Twp.22s-R12w
Stafford County - Kansas

0	-	50'	Sand
50	-	271'	Shale
271	-	651'	Red Bed
651	-	680'	ANHYDRITE
680	-	1530'	Shale-Shells-Salt
1530	-	2075'	Lime & Shale
2075	-	2570'	Shale
2570	-	2775'	Shale & Shells
2775	-	3100'	Lime & Shale
3100	-	3143'	Lime
3143	-	3277'	Shale-Lime-HEEBNER
3277	-	3293'	Lime-Shale BROWN LIME
3293	-	3538'	Lime - Shale LANSING
3538	-	3586'	Chert VIOLA
3586	-	3639'	Shale SIMPSON
3639			R.T.D.

ELEVATION: 1863 D.F. 1865 K.B.

FORMATION DATA


ANHYDRITE	651
HEEBNER	3141
BROWN LIME	3277
LANSING	3293
VIOLA	3538
SIMPSON	3586
R.T.D.	3639

SURFACE CASING: Set 271'
of 8-5/8" casing with
200 sacks cement.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Lewis O. Chubb of lawful age, does swear that the facts and statements herein contained are true and correct to the best of his knowledge.


Lewis O. Chubb

Subscribed and sworn to before me this 12th day of March, 1962.


Clair E. Stimson
NOTARY PUBLIC

My Commission Expires: 6-24-63

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1962
CONSERVATION DIVISION