

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25959-00-00
Spot: N2NE Sec/Twnshp/Rge: 5-20S-23W
660 feet from N Section Line, 1320 feet from E Section Line
Lease Name: STUM-HARRIS "A" Well #: 1-5
County: NESS Total Vertical Depth: 4460 feet

Operator License No.: 34579
Op Name: COBALT ENERGY LLC
Address: 115 S. BELMONT #12 PO BOX 8037
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/10/2017 4:30 PM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Revd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8420

Proposed Plugging Method: 1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 245' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE
Date/Time Plugging Completed: 08/10/2017 6:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

Perfs:

1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 245' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY GLOBAL.

Plugged through: DP

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
AUG 18 2017
KCC DODGE CITY



INVOICED
AUG 30 2017