

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-099-19373-00-00  
Spot: SWSW Sec/Twnshp/Rge: 2-33S-17E  
655 feet from S Section Line, 4628 feet from E Section Line  
Lease Name: KERR-BLANKENSHIP TRUST Well #: 1  
County: LABETTE Total Vertical Depth: 962 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD   | 4.5  | 961        |             | 122 SX  |
| SURF   | 7    | 20         |             | 4 SX    |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/14/2017 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX R. ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG WITHIN 1' OF BTM OF CSG THEN "GEL" THE WELL UP (PMP IN A MIXTURE OF BENTONITE & WTR), FOLLOWED BY A 150' CMT PLUG ON BTM, PU TBG TO 600', PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP IN CMT & CIRC SAME TO SURF, POOH REST OF TBG & "TOP OFF" WELL W/ CMT. RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH" & CLEAN UP LOC.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 08/14/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" TBG TO 771', HIT RUBBER PLUG, PU TBG 1', "GEL'D THE HOLE UP" (PMPD IN A MIXTURE OF BENTONITE & WTR), FOLLOWD BY A 150' CMT PLUG ON BTM, PU TBG TO 400', PMPD IN A 50' CMT PLUG, PU TBG TO 252, PMPD IN & CIRC CMT TO SURF, POOH REST OF TBG, "TOPPED OFF" PROD CSG W/ CMT PRESS UP TO 150 PSI, SWI. THEN RI 1/2" TBG IN ANNULAS TO 257, CIRC CMT TO SURF, POOH 1/2" TBG, "TOP OFF" ANNULAS W/ CMT CMT FROM 771 TO 621, GEL SPACER FROM 621 TO 400, CMT FROM 400 TO 350, GEL SPACER FROM 350 TO 252, CMT FROM 252 TO SURF AND CMT FROM 257 TO SURFACE IN ANNULAS ("BACKSIDE") USED: 2, 100# SX OF BENTONITE, 1/2 SX OF COTTON SEED HULLS, AND 68 SX OF PORTLAND CMT W/ NO ADDITIVES.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 1   | 2   |      |          |

RECEIVED  
KCC DIST # 3  
AUG 24 2017  
CHANUTE, KS  
RH

Remarks: THIS WELL IS LISTED ON A COMPLIANCE AGREEMENT

Plugged through: TBG

District: 03

Signed Russell Hine  
(TECHNICIAN)

INVOICED  
AUG 30 2017