

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-19896-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 2-33S-17E
195 feet from S Section Line, 5018 feet from E Section Line
Lease Name: KERR-BLANKENSHIP TRUST Well #: 5
County: LABETTE Total Vertical Depth: 800 feet

Operator License No.: <u>5150</u>	String	Size	Depth (ft)	Pulled (ft)	Comment
Op Name: <u>COLT ENERGY INC</u>	PROD	2.375	794		93 SX
Address: <u>PO BOX 388</u> <u>IOLA, KS 66749</u>	SURF	6	20		3 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/14/2015 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Revd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN NOT "BULL HEAD" CMT SQUEEZE DWN THE 2 3/8" PROD CSG, WILL RIH 1" TBG TO WITHIN 1' OF BTM OF PROD CSG, PMP IN CMT AND CIRC SAME TO SURF, THEN POOH THE 1" TBG, "TOP OFF" THE PROD CSG W/ CMT, PRESS UP ON SAME AND SHUT THE WELL IN. RETURN AT A LATER DATE TO CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP THE LOCATION.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 08/15/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 1" TBG, HIT "STEEL" / "IRON" AT 758', PMPD CMT DWN SAME, PMPD IN 1 BBL CMT SLURRY THEN FLUID CIRC ON "BACKSIDE" OF 2 3/8" PROD CSG, PMPD IN 96 SX OF CMT, NO CMT RETURNS TO SURF (INSIDE PROD CSG OR "BACKSIDE"), SHUT DWN FOR THE DAY TO LET CMT SET UP OVER NIGHT, AFTER POOH THE TBG. NEXT DAY; RIH THE TBG, GOT TO 37', HIT CMT, PMPD IN CMT & CIRC CMT TO THE SURF, POOH TBG THEN RAN 1/2" TBG ON "BACKSIDE" (ANNULAS), HIT TOP OF CMT AT 57', PMPD IN CMT & CIRC SAME TO SURF, POOH THE 1/2" TBG, "TOPPED OFF" PROD CSG AND ANNULAS. USED: 1/2 SX OF COTTON SEED HULLS AND 114 TOTAL SX OF PORTLAND CMT W/ NO ADDITIVES

Perfs:

Top	Bot	Thru	Comments
760	804		

RECEIVED
KCC DIST # 3
AUG 24 2017
CHANUTE, KS
RH

Remarks: THIS WELL IS LISTED ON A COMPLIANCE AGREEMENT

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)

INVOICED
AUG 30 2017