

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-19372-00-00

Spot: NENWSW

Sec/Twnshp/Rge: 2-33S-17E

1840 feet from S Section Line, 4336 feet from E Section Line

Lease Name: GREGORY L. SOUTHWEST Well #: 1

County: LABETTE

Total Vertical Depth: 772 feet

Operator License No.: 5150

Op Name: COLT ENERGY INC

Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	771		102 SX
SURF	7	22		3 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/15/2017 12:00 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Revd. from: REX R. ASHLOCK

Company:

Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 769', "GEL" WELL UP (PMP IN A MIXTURE OF BENTONITE & WTR) FOLLOWED BY A 150' CMT PLUG ON BTM, PU TBG TO 450', PMP IN A 50' CMT PLUG, PU TBG TO 250', PMP IN & CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, PRESS UP TO 200 PSI, AND SWL. RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "FLOW DEPTH", AND CLEAN UP LOC.

Plugging Proposal Received By:

Witness Type: NONE

Date/Time Plugging Completed: 08/15/2017 12:00 AM

KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" TBG, WASHED DWN LAST JT, HIT RUBBER CMT PLUG AT 769', PU TBG TO BE ABLE TO CIRC, "GEL'D THE WELL UP" (PMPD IN A MIXTURE OF BENTONITE & WTR) FOLLOWED BY A 100' CMT PLUG ON BTM, PU TBG TO 465', PMPD IN A 100' CMT PLUG, PU TBG TO 252', PMPD IN AND CIRC CMT TO SURF, POOH REST OF TBG, "TOPPED OFF" PROD CSG W/ CMT, PRESS UP TO 150 PSI, SWL CMT FROM 769 TO 669, GEL SPACER FROM 669 TO 465, CMT FROM 465 TO 365, GEL SPACER FROM 365 TO 250, CMT FROM 250 TO SURF. USED: 2, 100# SX OF BENTONITE, 1/2 SX OF COTTON SEED HULLS, 52 SX OF PORTLAND W/ NO ADDATIVES.

Perfs:

Top	Bot	Thru	Comments
737	742		

RECEIVED
KCC DIST # 3
AUG 24 2017
CHANUTE, KS

RH

INVOICED
AUG 30 2017

Remarks: THIS WELL IS LISTED ON A COMPLIANCE AGREEMENT

Plugged through: TBG

District: 03

Signed

Russell Hine
(TECHNICIAN)