

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40147-00-02
Spot: NWSWNE Sec/Twnshp/Rge: 17-29S-8E
3576 feet from S Section Line, 2321 feet from E Section Line
Lease Name: WEHRMAN Well #: 7
County: BUTLER Total Vertical Depth: 2733 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2692		30 SX
SURF	8.625	42		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICH CLARK/HAYS WILSO Company: CROWN ENERGY CO Phone: (405) 526-0111

Proposed Plugging Method: AS PER KCC RULES & REGS/CIBP @ 2630 W/5 SXS. PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 08/15/2017 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 2600', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SKS 60/40POZMIX 4% GEL, 100# HULLS & DISPLACED IN CASING. FLUID STAYED @ SURFACE. PULLED TUBING @ 270', QWS ESTABLISHED CIRCULATION MIXED & PUMPED 160 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. SWEDGED INTO CASING 7 PUMPED 5 SXS. SIP 200#.

Perfs:

Top	Bot	Thru	Comments
2696	2733	OH	

Remarks: COMPLIANCE/DENIED TA

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

INVOICED

AUG 30 2017