

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-00615-00-00  
Spot: SESENW Sec/Twnshp/Rge: 17-29S-8E  
2938 feet from S Section Line, 2990 feet from E Section Line  
Lease Name: WEHRMAN Well #: 1  
County: BUTLER Total Vertical Depth: 2715 feet

Operator License No.: 33192  
Op Name: CROWN ENERGY COMPANY  
Address: 1117 N.W. 24TH ST.  
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	2698		0 SX
SURF	8	100		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/08/2017 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICH CLARK/JOHN HILL/C Company: CROWN ENERGY CO Phone: (405) 526-0111

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP @ 2630' W/S SXS PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/09/2017 5:00 PM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

SET CIBP @ 2600', DUMP BAILED. 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 250'-251'. RIH W/TUBING @ 270' QWS ESTABLISHED CIRCULATION MIXED & PUMPED 115 SX 60/40 POZMIX 4 % GEL TO SURFACE. LAYED DOWN TUBING. SWEDGED INTO 5 1/2" CASING, MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. 8-9-2017 TOPPED WELL BACK TO SURFACE W/S SXS.

**Perfs:**

Top	Bot	Thru	Comments
2680	2715	OH	

Remarks: COMPLIANCE/DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

INVOICED  
AUG 30 2017