

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-141-20452-00-00
Spot: E2SWNWSE Sec/Twnshp/Rge: 31-8S-12W
1650 feet from S Section Line, 2275 feet from E Section Line
Lease Name: BRANT Well #: 1
County: OSBORNE Total Vertical Depth: 4006 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3273		170 SX
SURF	8.625	220		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2017 9:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK OIL & OPERATING, LLC
Proposal Rcvd. from: IVAN R. EDSALL Company: DREILING OIL INC Phone: (785) 625-8327

Proposed Plugging Method: Ordered 225 sx 60/40 pozmix 4% gel cement, 16 sx gel and 200 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/17/2017 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked to casing and pumped 55 bbl of salt water at 3 bpm at 500#. Pumped 50 sx cement w/100 # hulls followed by 16 sx gel followed by 75 sx cement w/100 # hulls. Pressure climbed to 850 psi. Shut in pressure 350 psi. Dug out braden head and pressured up to 450 psi. No fluid was moved.

GPS: 39.31197 -098.70200

Perfs:

Top	Bot	Thru	Comments
3023	3025		

KCC WICHITA
AUG 24 2017
RECEIVED

Remarks: QUALITY CEMENTING SERVICE TICKET # 1593

Plugged through: CSG

INVOICED
AUG 30 2017

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

AUG 18 2017