

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20420-00-00
Spot: NESW Sec/Twnshp/Rge: 9-31S-17W
1936 feet from S Section Line, 3075 feet from E Section Line
Lease Name: YOST Well #: 23-9
County: COMANCHE Total Vertical Depth: 5166 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4738		WITH 2 SX CMT
PROD	4.5	5166	0	WITH 430 SX CMT
SURF	8.625	540		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/07/2017 10:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4860' WITH 2 SX CMT. PRESSURE TEST CASING. PERFORATE AT 1050' & 590'. RUN TBG TO 1050' & PUMP 10 SX GEL, 50 SX CMT (100# HULLS IN LAST 25 SX CMT). PULL TBG TO 590' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF WITH CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/08/2017 9:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

8/7/17: SQUEEZED CASING LEAKS AT 545-576' & 4165-4597' IN 2014. STILL TIGHT LEAKS. COULD NOT GET CIBP PAST 4738' SO SET IT THERE WITH 2 SX CMT. CASING TEST PROVED AT TIGHT LEAK AT 1/2 BPM AT 400#. PERFORATED AT 1050' & 590'. RAN TBG TO 1061' & ESTABLISHED PUMP RATE OF 3 BPM AT 700#. PUMPED 10 SX GEL, 25 SX CMT, THEN 25 SX CMT WITH 100# HULLS. PULLED TBG TO 593' & PUMPED 125 SX CMT. HAD GOOD CIRCULATION UNTIL RETURNS STARTED SHOWING SIGNS OF CMT THEN LOST CIRCULATION. PULL TBG. WILL TAG CMT. 8/8/17: TAGGED TOC AT 764'. RAN TBG TO 593' & CIRCULATED NEAT CMT WITH 3% CC & 100# HULLS TO SURFACE WITH 50 SX. PULLED TBG & TOPPED OFF WITH 25 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4910	5065		

INVOICED
AUG 30 2017
INVOICED
AUG 31 2017

Remarks: USED 60/40 POZMIX 4% GEL & NEAT CMT WITH 3% CC BY BASIC ENERGY SERVICES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
AUG 10 2017
KCC DODGE CITY