

State of Kansas



15-009-07403-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1967

CONSERVATION DIVISION
Wichita, Kansas

2-3-1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lynn O. Duke of Duke Drilling Company has this
date requested permission to plug the following described well:

Mr. Lynn O. Duke guarantees payment of the plugging fee.

Operator's full Name: Duke Drilling Company

Complete Address: Box 823, Great Bend, Kansas

Lease Name: Hitchmann Well No. # 1

Location: NE NW NE Sec. 28 Twp. 16 Rge. 12 (E)(W) W

County Barton Total Depth 3399 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. D. B. Pully was instructed to plug the well as follows:

8 5/8" 310' Cwc.

Sanded hole back to 3350' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mud to 300', set rock bridge, & displaced 25 sax cement.

Mud to 40', set rock bridge, & displaced 10 sax cement, cementing to

base of cellar.

Very truly yours,

Don Adrian
Conservation Division Agent