

To: 1 120994 12-13
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-185-00447-0000
API NUMBER 15- Spud date 12/30/50
SE SE SW, SEC. 27, T 21 S, R 14 W/E
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4058
Operator: American Warrior, Inc.
Name & Address: P.O. Box 399
Garden City, KS 67846

Lease Name Gates "B" Well # 1
County Stafford 123.11
Well Total Depth 3788 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor American Warrior, Inc. License Number 4058
Address P.O.Box 399, Garden City, KS 67846

Company to plug at: Hour: 9:30 a.m. Day: 13 Month: 12 Year: 19 94

Plugging proposal received from Kevin Wiles
(company name) American Warrior, Inc. (phone) 316-275-2963

were: 5 1/2" at 3783' w/150 sx cement, CIBP at 3770', 3625', & 3490', All perms below CIBP
1st plug pump 25 sx cement on bottom,
2nd plug circulate cement from Anhydrite.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 13 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug ran 110 joints of tubing and pumped 75 sx cement at 3455'
in 5 1/2" casing.

2nd plug laid down 82 joints of tubing and pumped 300 sx cement at 869'.
Cement circulated through 5 1/2" casing and 8 5/8" surface casing.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (client) HEREBY observe this plugging.

DATE 1-3-95

INV. NO. 41937

Signed Duane Rankin
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
DEC 16 1994
CONSERVATION DIVISION
WICHITA, KANSAS