

1 120056

12-4-87 15.185.20536.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION S/2 NE SE SW, SEC. 27, T 21 S, R 14 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill completion date 11/9/74

Approx. 825' feet from S section line

2970 feet from E section line

Lease Name Gates "B" Well # 7

County Stafford 120.35

Well Total Depth 3703 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 286

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Operator: Kaiser-Francis Oil Company

Name & Address P.O. Box 21468

Tulsa, OK 74121-1468

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kaiser-Francis Oil Company License Number 6568

Address P.O. Box 21468, Tulsa, OK 74121-1468

Company to plug at: Hour: 9:30 a.m. Day: 4 Month: 12 Year: 19 87

Plugging proposal received from John Glenn

(company name) Kaiser-Francis Oil Company (phone) 918-494-0000

were: 4 1/2" at 3703' PBTD 3670' Top perf 3532'

1st plug sand back to 3480' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 a.m. Day: 4 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3480' and dumped 4 sx cement on top of sand
with dump bailer,

2nd plug pumped in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10

sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1987
10-9-87
CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1850' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 12-9-87

Signed *Richard Lacey*
(TECHNICIAN)

INV. NO. 19241
12-4