

To: 1 120579
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-13 15.185.10804.0000
API NUMBER 15- NA

NE NE SW, SEC. 27, T 21 S, R 14 W/E
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568
Operator: Kaiser-Francis Oil Company
Name & Address: P.O. Box 666
Ellinwood, KS 67526

Lease Name Gates "B" Well # 4
County Stafford 122.85
Well Total Depth 3780 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kaiser-Francis Oil Company License Number 6568

Address P.O. Box 666, Ellinwood, KS 67526

Company to plug at: Hour: 2:30 p.m. Day: 13 Month: 6 Year: 19 91

Plugging proposal received from John Glenn

(company name) Kaiser-Francis Oil Company (phone) 316-564-3214

were: 5 1/2" at 3775' w/150 sx cement, Pump & mud anchor in well PBTID 3563', Fished tubing down to 758', 5 1/2" casing parted at 490', 5 1/2" casing squeezed at 1387-1400' w/600 sx cement, packer set in 5 1/2" casing at 3276'

Clean up well bore to Anhydrite and fill with cement through tubing.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7 p.m. Day: 13 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug ran tubing to 752' and pumped 6 sx gel and 470 sx cement, cement circulated in 5 1/2" X 8 5/8",

2nd plug layed down tubing and filled 5 1/2" X 8 5/8" with 30 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. No casing recovery. CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 6-20-91

Signed Steve Durrant (TECHNICIAN)

INV. NO. 32212

6-13